

PROCESS EQUIPMENT



Altus is a leading manufacturer, designer and fabricator of process and production equipment. We have the experience and expertise to engineer top calibre oilfield production equipment that meets the highest customer and government specifications and standards, including ASME, ANSI and API. Our specialized engineering, drafting and procurement capabilities enable us to create a wide range of custom products which are tailored to the specific needs of our customers.

We provide:

- Pressure Vessels
- Separator Packages
- Lineheater Packages
- Satellite Packages
- Slug Catchers/Blowcase Packages
- Gas Metering Packages
- Heat Medium Skids



PROCESS EQUIPMENT



16" x 7' 6" x 1440# Separator Package

- Sweet or Sour Service
- 16" OD x 7'-6" Seam/Seam Vessel
- 1,440 psig M.A.W.P. @ 100°F
- -20°F M.D.M.T.
- 1/16" Corrosion Allowance
- Vertical Three (3) Phase Style,
c/w 2 Phase Controls
- ASME "U" Stamp, B.C., AB., SASK. Registered
- 2" 600# ANSI Simplex Meter Run
- Two (2) Pen Recorder
c/w a Three (3) Valve Manifold
- Manual Globe Valve Downstream of Meter Run
- Fuel Gas Scrubber c/w High Level Shut-Off Valve
- 6'-0" Wide x 12'-0" Long Structural Steel
Skid Base
- 6' x 8' Self Framing Galvanized Steel Building
- Catalytic Heater c/w Start-Up Cables
- Prime & Finish Paint

CONTACT YOUR ACCOUNT MANAGER FOR CURRENT PRICING.
Equipment descriptions above are basic and generic. Several options are available
for customizing the equipment offered to meet client specific requirements.

PROCESS EQUIPMENT



24" x 7' 6" x 1440# Separator Package

- Sweet or Sour Service
- 24" OD x 7'-6" Seam/Seam Vessel
- 1,440 psig M.A.W.P. @ 100°F
- -20°F M.D.M.T.
- 1/16" Corrosion Allowance
- Vertical Three (3) Phase Style,
c/w 2 Phase Controls
- ASME "U" Stamp, B.C., AB., SASK. Registered
- 3" 600# ANSI Simplex Meter Run
- Two (2) Pen Recorder
c/w a Three (3) Valve Manifold
- Manual Globe Valve Downstream of Meter Run
- Fuel Gas Scrubber c/w High Level Shut-Off Valve
- 6'-0" Wide x 12'-0" Long Structural Steel
Skid Base
- 6' x 8' Self Framing Galvanized Steel Building
- Catalytic Heater c/w Start-Up Cables
- Prime & Finish Paint

CONTACT YOUR ACCOUNT MANAGER FOR CURRENT PRICING.

Equipment descriptions above are basic and generic. Several options are available for customizing the equipment offered to meet client specific requirements.

PROCESS EQUIPMENT



16" x 7' 6" x 1440# Separator Package c/w 100BBL

Aboveground Double Wall Storage Tank

- Sweet Service
- 16" OD x 7'-6" Seam/Seam Vessel
- 1,440 psig M.A.W.P. @ 100°F
- -20°F M.D.M.T.
- 1/16" Corrosion Allowance
- Vertical Three (3) Phase Style, c/w 2 Phase Controls
- ASME "U" Stamp, B.C., AB., SASK. Registered
- 3" 600# ANSI Simplex Meter Run
- Two (2) Pen Recorder c/w a 3-Valve Manifold
- Manual Globe Valve Downstream of Meter Run
- Fuel Gas Scrubber c/w High Level Shut-Off Valve
- Skid Mounted 100BBL A/G. DW. Storage Tank c/w Manway, Thief Hatch, Ladder and Monitor Detection System for Floor and Shell.
- 8'-0" Wide x 23'-0" Long Structural Steel Skid Base
- Self Framing Galvanized Steel Building
- Catalytic Heater c/w Start-Up Cables
- Prime & Finish Paint

CONTACT YOUR ACCOUNT MANAGER FOR CURRENT PRICING.

Equipment descriptions above are basic and generic. Several options are available for customizing the equipment offered to meet client specific requirements.

PROCESS EQUIPMENT



24" x 7' 6" x 1440# Separator Package c/w 100BBL

Aboveground Double Wall Storage Tank

- Sweet Service
- 16" OD x 7'-6" Seam/Seam Vessel
- 1,440 psig M.A.W.P. @ 100°F
- -20°F M.D.M.T.
- 1/16" Corrosion Allowance
- Vertical Three (3) Phase Style, c/w 2 Phase Controls
- ASME "U" Stamp, B.C., AB., SASK. Registered
- 3" 600# ANSI Simplex Meter Run
- Two (2) Pen Recorder c/w a 3-Valve Manifold
- Manual Globe Valve Downstream of Meter Run
- Fuel Gas Scrubber c/w High Level Shut-Off Valve
- Skid Mounted 100BBL A/G. DW. Storage Tank c/w Manway, Thief Hatch, Ladder and Monitor Detection System for Floor and Shell.
- 8'-0" Wide x 23'-0" Long Structural Steel Skid Base
- Self Framing Galvanized Steel Building
- Catalytic Heater c/w Start-Up Cables
- Prime & Finish Paint

CONTACT YOUR ACCOUNT MANAGER FOR CURRENT PRICING.
 Equipment descriptions above are basic and generic. Several options are available for customizing the equipment offered to meet client specific requirements.